

# MASY-HF

High Flow Manifold Assembly



The MASY-HF High Flow Manifold Assembly is designed to be an all-in-one approach to chemical injection. Constructed with quality components to meet customers' requirements.

## Manifold Assembly Consists of

- HFF High Pressure Filter
- CVA-11080 High Flow Check Valve
- 4" 0-5000 Psi Liquid Filled Gauge
- 5000 Psig Tee or Cross
- 5000 Psig Needle or Ball Valves
- Assembly Configurations Vary Depending on Customer Requirements
- All Fittings Used on the Assembly are 316 SS
- Each Unit is Completely Assembled, Leak Tested and Individually Boxed

## Features

- 5000 Psig MAOP
- All 316 SS Construction
- 100 Mesh or 25 Micron Standard
- Cleanable & Replaceable Element
- Check Valve
- Made in the USA